

Republic of the Philippines

BULACAN AGRICULTURAL STATE COLLEGE REQUEST FOR QUOTATION

Document No.: BASC-PRO-QSF-02

Rev. No.: 00

Effectivity Date: 06/03/2019

Project Reference Number: Name of the Project: Location of the Project:

Date:	
Quotation No	

Company Name	
Address	
Please quote your lowest price on the item/s listed below, subject to the General Conditions on the	
last page, stating the shortest time of delivery and sumbit your quotation duly signed by your representative not later than	

in the return envelope attached herewith.

MANDY D. BERNARDO **Procurement Officer**

NOTE:

1. THE APPROVED BUDGET FOR THE CONTRACT IS _

2. ALL ENTRIES MUST BE TYPEWRITTEN.

3. DELIVERY PERIOD WITHIN _____ CALENDAR DAYS.

4. WARRANTY SHALL BE FOR A PERIOD OF three (3) MONTHS FOR NON-EXPENDABLE SUPPLIES ONE (1) YEAR NON-EXPENDABLE SUPPLIES FROM DATE ACCEPTANCE BY THE PROCURRING ENTITY.

_ CALENDAR DAYS. 5. PRICE VALIDITY SHALL BE FOR A PERIOD OF $_$

6. PHILGEPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION.

7. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATION OF

THE PRODUCT BEING OFFERED.

TEM No.	Unit	ITEM & DESCRIPTION	QTY	UNIT PRICE	TOTA
		Excavation			
1		Excavation including maintaining and supporting sides and			
		keep free from water, mud, and fallen materials by bailing,			
	lot	pumping or otherwise	1		
2 lot		Prepare site by stripping top 150 mm of soil to remove all			
	lot	debris including sand (if any) from site and carting away spoil	1		
	100	Pit excavation commencing at reduced levels depth not	1		
3	lot	exceeding 1.50m deep	1		
4	lot	Extra-over for excavation in soft rock and in hard rock	1		
5	lot	Removed suplus excavated material from site	1		
6	lot	Backfill around foundation including compaction	1		
		Water Tank Pedestal (2mx2mx.15m) and Sump pit			
		150mm thick concrete pedestal with 20mm thick maximum			
7	lot	aggregate size	1		
8	lot	Construction of Sump Pit (1.5x1.5x1.5m)	1		
		Pump House			
9	lot	Construction of 1.5mx1.5m RC pumphouse	1		
		Water Tank and accessories			
10		Supply and installation of pressurize water tank with a			
		capacity of 1000 gallons (inclusive of supply of valves such	1		
	lot	as pressure relief valve, vacuum relief valve, etc.)			
		Water Pumps motor and accessories			
		Suuply and installation of 4" submersible pump (3hp), with			
11		automatic pressure controller, leaf guard swivel outlet,	1		
	lot	corresponding valves, perforated pipe, etc.)			
12		Supply and installation of booster pump (1.5hp), inclusive	1		
	lot	of auto shut off pressure switch and valves			
		Water Pumps motor and accessories			
13	pcs	B.I. Pipe 6"Ø Sch.40	1		
14	pcs	G.I. Pipe 4"Ø Sch.40	15		
15	pcs	G.I. Pipe 2"Ø Sch.40	12		
16	pcs	France Coupling 2"	10		
17	pcs	Elbow 2"	8		
18	pcs	Ball valve 2"	2		Balanta
19	pcs	Union Patente 2"	1		
20	pcs	Nipple 2"x4"	4		
21	pcs	G.I. Tee 2"	1		
22	set	Controller Panelboard	1		
23	roll	Royal chord 10/2C	1		
24		Panelboard	1		
25	set				
	set	Housing 2 /4" PDP DV	1		
26	pcs	3/4" PPR Pipe	60		
27	pcs	Pressure gauge	3		
28	pcs	Gate valve	5		
29	pcs	Check valve	2		
30		Other consumables and miscellaneous (including pvc			
	lot	fixtures, etc.)			
31		Labor			

	Item No.	Item No.
d and Mode		
ery Period:		
anty:		
Validity:		
After having	carefully read and accepted your General Conditions, I/Wo	e quote on the item at prices noted above.

Printed Name / Signature

Tel. No. / Cellphone No. e-mail address

Date